No.	Items of work	Per	Rate	Quantity	Cost
	Constructing Sheep-Pen.				
1	Earthwork excavation for foundation ..	C.yd.		10	
2	Burnt stone slabs new 4″ to 5″ roughly dressed and fixed	S.ft.		210	
3	Carting and fixing old iron rails available at Serum Institute	R.ft.	Rs. a. p.	87	
4	Metal concrete in mortar	C.ft.		252	
5	New steel rafters 3″×5″ including fixing ..	Cwt.		13½	
6	Angle iron purlins 1½″ x 1½″ x ¼″	,,		13	
7	Cutting slopes in slabs	No.		12	
8	Cutting holes in girders to fix purlins ..	,,		36	
9	Iron bolts 6″×½″ for fixing iron rafters to stone pillars, including cutting holes ..	,,		12	
10	Fixing brackets at the ridge with bolts and nuts	,,		12	
11	Zinc sheet roofing with zinc bolts and nuts ..	Sqr.		12·19	
12	Zinc sheet ridge	R.ft.		53	
13	Empire fencing alround 4′ high complete ..	R.yd.		42	
14	Teakwood gate with iron work including painting and fixing	S.ft.		24	
15	Providing gravel flooring ½′ high including watering and tamping	Sqr.		8·00	
	III. Constructing Water Trough.				
1	Earthwork excavation	C.yd.		11	
2	Burnt brick in mortar	C.ft.		312	
3	Broken metal concrete in mortar ..	,,		171	
4	Cement plastering	Sqr.		6·21	

A. TANDONI RAO,
Executive Engineer.

TUMKUR DIVISION.

Notification, dated 17th December 1934.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M., on 12th January 1935, for repairing the Sri Prasanna Ramaswamy temple at Chicknaikanhalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of rupees 130 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for repairing the Sri Prasanna Ramaswamy Temple at Chicknaikanhalli," in default of which tender will be rejcted.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnect money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

Abstract estimate for repairing Sree Prasanna Rameswara Swami Temple at Chiknaikanhalli.

Sl. No.	Items of work	Unit	Quantity	Rate
1	Dismantling old masonry and concrete over the roof and removing debris	C.ft.	1972	
2	Removing and refixing the slabs of walls ..	S.ft.	342	
3	Burnt brick in chunam	C.ft.	1927	
4	Removing roots and plants grown inside walls	Lumpsum	..	
5	Removing thick slab over sukanasi for sky light	Sqr.	0·70	
6	Lifting and carrying the slabs below and refixing	,,	0·70	
7	Burnt stone slabs dressed 6″ thick new ..	Sq.ft.	212	
8	Plastering with chunam	Sqr.	32·42	
9	Teak wood wrought and put up complete ..	C.ft.	9	
10	Teak wood doors with frames and shutters 1½″ thick plank iron work pointing, etc., complete	S.ft.	39	
11	Teak wood windows with iron bars and sunshade	,,	45	
12	Plastering with vajragare over the roof with 4″ new concrete	Sqr.	30·35	
13	Flooring with burnt stone slabs 3″ thick dressed over existing concrete with cement pointing.	S.ft.	110	
14	Filling in holes and cracks with brick jelly concrete	C.ft.	200	
15	Providing pucca terrace over sky light ..	Sqr.	1·00	
16	Do 6″ cornice for the roof	R.ft.	42	
17	Providing dwarf parapet including plastering..	C.ft.	40	
18	Removing plant and roots and applying rent eradicating mixture over Gopuram and refixing kalasam with gold gilt, etc. ..	Lumpsum	..	
19	Scaffolding charges for plastering Gopuram and repairing walls outside	,,	..	
20	Chunam pointing	Sqr.	66·39	
21	Removing and refixing old slabes to proper level and chunam pointing	,,	24·8	
22	Clearing thorns and levelling ground ..	Lumpsum	..	
23	Repairing panchagram or basement with chunam pointing	Sqr.	7·80	
24	Scraping the decayed old mortar of the parapet wall and again plastering	,,	13·00	
25	Repairing.....five sides	Lumpsum	..	
26	Urgent and unforeseen works	,,	..	
27	White washing, 2 coats	,,	..	
28	Sundry repairs to kitchen	,,	..	

N. G. KRISHNA IYENGAR,
Executive Engineer.